



RUTLAND COUNTY
GARDEN FURNITURE

Hand-Crafted

ASSEMBLY INSTRUCTIONS

RIDLINGTON COAL BUNKER

Before you commence the assembly process we recommend that you read these instructions thoroughly beforehand to familiarise yourself with the assembly process and to also check that you have the correct components. If for any reason you need assistance, you can find our contact details on the final page of these instructions.

We highly recommend that any assembly is carried out on a flat, level surface if possible and that you use another person to assist you if necessary.

PACKAGE CONTENTS

1 x Base
2 x Side panels
1 x Back panel
1 x Front panel
1 x Roof panel
Steel cover panel(s)
75mm & 65mm screws
50mm Black hinge screws

TOOLS REQUIRED

Electric screwdriver with No2 Pozidrive bit
Or No2 Pozidrive Screwdriver
Supplied temporary spacer bar



THE RIDLINGTON COAL BUNKER

RIDLINGTON COAL BUNKER

Step 1



Place the base on a flat, level surface as shown.

Step 2



Now offer up one of the end panels, slotting it over the base as shown in the image...

Step 3



...before securing it in place using the 3 of the 50mm screws

Step 4



Locate the back panel on the rear edge of the base...

RIDLINGTON COAL BUNKER

Step 5



..aligning its front edge from top to bottom with the side panel batten as shown.

Step 6



Secure in place using 3 x 65mm screws, working your way from top to bottom.

Step 7



Now secure the bottom of the back panel to the base using more of the 50mm black screws .

Step 8



Place the supplied temporary spacer bar along the front of the base before locating the 2nd side panel in place, making sure both side panels are touching the spacer bar. Now secure the side panel to the base and back panels as before and then remove the spacer bar.

RIDLINGTON COAL BUNKER

Step 9



Now slide the front panel into place between the side panel uprights as shown above.

Step 10



After ensuring that the front panel frame is flush with the side panel batten, attach the front panel in place using 2 x 65mm screws per side in the top 2 holes...

Step 11



...before securing the lower section from outside of the store using the pre-drilled hole to locate the 75mm screw. Repeat the process to secure the other side panel to the front panel.

Step 12



Complete fixing the front panel in place by adding a single 50mm black screw beneath the cover panel aperture. (The double version will require a screw beneath each aperture.)

RIDLINGTON COAL BUNKER

Step 13



Now place the hinged roof panel in place, ensuring that it is aligned both centrally *and* flush with the back edge of the uprights as shown, before fixing in place with 2 x 65mm screws on both sides.

Step 14



Slide the steel cover panel(s) between the two runners on the front panel..

Step 15



Your Ridlington Coal Bunker is now complete.

WE HOPE THAT YOU FOUND YOUR PRODUCT QUICK AND EASY TO ASSEMBLE BUT IF NOT AND YOU REQUIRE ANY FURTHER ASSISTANCE OR HAVE ANY QUESTIONS YOU CAN CONTACT US BY TELEPHONE ON: **01778 440803**
EMAIL: INFO@RUTLANDCOUNTYGARDENFURNITURE.CO.UK
WWW.RUTLANDCOUNTYGARDENFURNITURE.CO.UK

Rutland County Garden Furniture Ltd, Ashbourne House, 2 Dovecote Meadows,
Aslackby, Sleaford, Lincs, NG34 0HZ.
Company No: 7670072 VAT No: 151744027